

APPROVED SCHEDULE - B

E/BTP/BBMP/E-PMT/20/2017-18, Date:12.02.2018

Improvements of roads, drains and culverts at Kodigehalli ward no. 8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				N N Sreenivasaiah	
				In Figures	In Words
1	768.29	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification.	cum	174.0	Rupees One Hundred Seventy Four Only
2	125.57	KSRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	4990.0	Rupees Four Thousand Nine Hundred Ninety Only
3	47.52	KSRB 5.2-3: Providing and constructing granite size stone masonry in foundation cement mortar 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications.	cum	4141.0	Rupees Four Thousand One Hundred Forty One Only
4	79.2	KSRB 15.1.1 Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	96.0	Rupees Ninety Six Only
5	18.46	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5381.0	Rupees Five Thousand Three Hundred Eighty One Only
6	217.37	Providing laying plain / reinforced cement concrete for Box Drain walls of thickness 10cm to 20 cm including centering shuttering form work etc. complete as per approved drawing and design MORTH Specification No. 1500,1700,2200 PCC M 20 Grade upto 0.75 m height using concrete mixture	cum	10293.0	Rupees Ten Thousand Two Hundred Ninety Three Only
7	11.96	KSRB - 4.9.2: Providing TMT steel reinforcement Fe500 for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	59939.0	Rupees Fifty Nine Thousand Nine Hundred Thirty Nine Only
8	595.95	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	1711.0	Rupees One Thousand Seven Hundred Eleven Only
9	89.1	Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	4769.0	Rupees Four Thousand Seven Hundred Sixty Nine Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
4/12